



जम्मू केंद्रीय विश्वविद्यालय Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

=====

No: CUJ/W/2022/3933

Date: 18.11.2022

.....
.....
.....

Sub: - Quotation.

Name of Work: Structural Steel work in 100 bedded Boys Hostel at CUJ campus.

Dear Sir,

CUJ invites quotation for Structural steel fabrication works at the campus of Central University of Jammu, Rahya Suchani, Bagla. You are requested to quote the overall percentage for complete work: "At Par", or "Above" or "Below" in figures, as well as, in words (including GST) of the enclosed format. In case of any discrepancy noticed in the quoted percentage, the percentage quoted in words shall be considered. Electricity charges @ 1% shall be deducted in case the vendor uses the electricity from CUJ resources.

Terms and Conditions:-

1. The completion period is 21 days (Twenty one) from the date of issue of work order.
2. The Estimated cost of work is Rs99441/- (Rupees ninety nine thousand four hundred forty one only)
3. Last date of submission of Quotation is 02.12.2022 at 12:00 hrs
4. Date of Opening of Quotation is 02.12.2022 at 15:00 hr or as decided by the convenor LPC.
5. Validity of Quotation is 45 days from the date of opening of Quotation.
6. Bidders quoting percentage item wise shall be summarily rejected. Rates are inclusive of all taxes, hiring of machinery like hydra for shifting, loading Unloading, transportation Octroi, cess, GST etc. Rates are FOR at site.
7. Statutory deductions like TDS & Labour cess as per applicable rates will be made from the contractor's bill.
8. Rates quoted shall be firm and fix and no escalation shall be provided throughout the currency of the period of work.
9. The Quantities shown are tentative and the quantity may increase or decrease with in permissible limits at the time of actual execution of work.
10. Payment shall be made as per the actual work done based on actual measurement at site.
11. All the materials used in the work shall be ISI marked.
12. No advance payment will be made.
13. GST Bill should be provided.



जम्मू केंद्रीय विश्वविद्यालय Central University of Jammu


राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

=====

14. CUJ reserves the right to cancel the work before the commencement of work or at any stage of execution if found substandard or not as per required specifications.
15. Payment shall be made through RTGS/NEFT.
16. Work is to be executed as per CPWD Specification 2019 VOL-1&VOL-2 with up-to-date correction slip
17. If the bidder withdraws from the work after coming out as Lowest within the bid validity period, the bidder shall be debarred from applying for further works in the University for period of two year.
18. Bidder may visit the site of place before quoting the rates and familiarise himself with the site conditions.
19. Bidders are required to submit following document along with Quotation:
 - i. Covering letter in Company letter head format.
 - ii. GST Registration/ Pan Card/Aadhar Card
 - iii. Contact Information of bidder (Complete address and Phone no.)

Encl: As Above

CC: Guard File
Notice Board


(Er. Vishal Bargotra)
Executive Engineer




जम्मू केंद्रीय विश्वविद्यालय Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

Bill of Quantities

| | Item Description | Unit | Qty | Rate(Rs.) | Amount (Rs) | DSR ref |
|---|--|------|-----|-----------|-------------|---------|
| 1 | Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerincharge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. | sqm | 42 | 671.55 | 28205.1 | 12.5 |
| 2 | Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including, cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete Hot finished seamless type tubes | kg | 495 | 120 | 59400 | 10.16.2 |
| 3 | Providing & Fixing welded steel wire mesh of required width and aperture and of required guage.12 guage 50mmX50mm | m2 | 22 | 538 | 11836 | MR |
| | Total | | | | 99441.10 | |

Say Rs 99441.0(Rupees Ninety Nine thousand four hundred forty one only)


15/11/2022



जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu


राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

Quotation Form

Name of Work: Structural Steel work in 100 bedded Boys Hostel at CUJ campus

Estimated Cost: Rs99441.00/- (Rupees ninety nine thousand four hundred and forty one (Inclusive of GST))

| Name of Work | Quote Percentage (Above/At Par/Below) on Estimated cost | |
|--|---|----------|
| | In figures | In words |
| Estimated Cost: Rs99441.00/- (Rupees ninety nine thousand four hundred and forty one (Inclusive of GST)) | | |


18/11/2022

Signature & Stamp of the vendor