



जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu
राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

No: CUJ/W/2022/3892

Date: 10.11.2022

.....
.....
.....

Sub: - Quotation.

Name of Work: Creation of one classroom in community college of Central University of Jammu.

Dear Sir,

CUJ invites quotation for creation of one classroom at Community college of Central University of Jammu, Rahya Suchani, Bagla. The work involves dry wall partition works. You are requested to quote the overall percentage for complete work: "At Par", or "Above" or "Below" in figures, as well as, in words (including GST) of the enclosed format. In case of any discrepancy noticed in the quoted percentage, the percentage quoted in words shall be considered. Electricity charges @ 1% shall be deducted in case the vendor uses the electricity from CUJ resources.

Terms and Conditions:-

1. The completion period is 14 days (Twenty one) from the date of issue of work order.
2. The Estimated cost of work is Rs 91000.00 (Rupees Ninety one Thousand) GST inclusive
3. Last date of submission of Quotation is 18/11/2022 at 12:00 hrs
4. Date of Opening of Quotation is 18/11/2022 at 15:00 hr.
5. Validity of Quotation is 45 days from the date of opening of Quotation.
6. Bidders quoting percentage item wise shall be summarily rejected. Rates are inclusive of all taxes, loading Unloading, transportation Octroi, cess, GST etc. Rates are FOR at site.
7. Statutory deductions like TDS & Labour cess as per applicable rates will be made from the contractor's bill.
8. Rates quoted shall be firm and fix and no escalation shall be provided throughout the currency of the period of work.
9. The Quantities shown are tentative and the quantity may increase or decrease with in permissible limits at the time of actual execution of work.
10. Payment shall be made as per the actual work done based on actual measurement at site.
11. All the materials used in the work shall be ISI marked.
12. No advance payment will be made.
13. GST Bill should be provided.




जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

- =====
14. CUJ reserves the right to cancel the work before the commencement of work or at any stage of execution if found substandard or not as per required specifications.
 15. Payment shall be made through RTGS/NEFT.
 16. Work is to be executed as per CPWD Specification 2019 VOL-1&VOL-2 with up-to-date correction slip
 17. If the bidder withdraws from the work after coming out as Lowest within the bid validity period, the bidder shall be debarred from applying for further works in the University for period of two year.
 18. Bidders are required to submit following document along with Quotation:
 - i. Covering letter in Company letter head format.
 - ii. GST Registration/ Pan Card/Aadhar Card
 - iii. Contact Information of bidder (Complete address and Phone no.)

Encl: As Above

CC: Guard File
Notice Board


10/11/2022

(Er. Vishal Bargotra)

Executive Engineer



जम्मू केंद्रीय विश्वविद्यालय Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

BOQ

S No	Description	Unit	Qty	Rate (Rs) (GST Inclusive)	Amount (Rs)	DSR Ref
1	9.105 Providing and fixing partition upto ceiling height consisting of G.I. frame and required board, including providing and fixing of frame work made of special section power pressed/ roll form G.I. sheet with zinc coating of 120 gms/sqm(both side inclusive), consisting of floor and ceiling channel 50mm wide having equal flanges of 32 mm and 0.50 mm thick, fixed to the floor and ceiling at the spacing of 610 mm centre to centre with dash fastener of 12.5 mm dia meter 50 mm length or suitable anchor fastener or metal screws with nylon plugs and the studs 48 mm wide having one flange of 34 mm and other flange 36 mm and 0.50 mm thick fixed vertically within flanges of floor and ceiling channel and placed at spacing of 610 mm centre to centre by 6 mm dia bolts and nuts, including fixing of studs along both ends of partition fixed flush to wall with suitable anchor fastener or metal screws with nylon plugs at spacing of 450 mm centre to centre, and fixing of boards to both side of framework by 25 mm long dry wall screws on studs, floor and ceiling channel sat the spacing of 300 mm centre to centre. The boards are to be fixed to the frame work with joints staggered to avoid through cracks, M.S. fixing channel of 99 mm width (0.9 mm thick having two flanges of 9.5mm each) to be provided at the horizontal joints of two boards, fixed to the studs using metal to metal flat head screws, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, angle beads at corners (25 mm x 25 mm x 0.5 mm), joint finisher and two coats of primer suitable for board as per manufacture's specification and direction of engineer in charge all complete. 2 9.105.2 : 75mm overall thickness partition with 12.5 mm thick double skin tapered edged plain Gypsum plaster board conforming to IS: 2095: (part I): 2011 (Board with BIS certification marks) (Gypboard/saint gobainor like)	sqm	40	1530.05	61202	9.105
11	21.1.1.1 Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS:	Kg	22	433.95	9546.9	21.1.1.2

BE



जम्मू केंद्रीय विश्वविद्यालय Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

	1868, Minimum anodic coating of grade AC 15). For fixed portion of doors, windows,					
2	21.1.2.1 Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately);; For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) : Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15). For shutters of doors, windows & ventilators	kg	20	531.8	10636	21.1.2.1
	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)					
3	13.41 Distempering with first quality acrylic distemper having VOC content 50 gms/ litre of approved manufacturer of required shape and colour as per manufacturer specification complete. Two or more coats on new work.	sqm	70	92.75	6492.5	13.41
	Providing or fixing panelling or panelling particle board 12 mm thick plain particle board flat pressed 3 layered or graded wood particle board medium density grade 1 IS 3087 marked.	sqm	2.1	1399.88	2939.748	
	Total				Rs	90817.15

Say Rs. 91000/-

Rupees Ninety one Thousand only.



जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

Quotation Form

Name of Work: Creation of one classroom in community college of Central University of Jammu.

Estimated Cost: Rs91000/- (Rupees Ninety One thousand only) GST Inclusive

Name of Work	Quote Percentage (Above/At Par/Below) on Estimated cost	
	In figures	In words
Creation of one classroom in community college of Central University of Jammu.		
Estimated Cost: Rs91000/- (Inclusive of GST)		

Signature & Stamp of the vendor