



जम्मू केंद्रीय विश्वविद्यालय Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba – 181143, Jammu (J&K)

=====

No: CUJ/W/2022/4011

Date: 16.12.2022

.....
.....
.....

Sub: - Quotation.

Name of Work: Providing floor finish and basic toilet facility in security complex.

Dear Sir,

CUJ invites quotation for civil works like providing floor finishes and basic toilet facility in security complex, Rahya Suchani, Bagla. You are requested to quote the overall percentage for complete work: "At Par", or "Above" or "Below" in figures, as well as, in words (including GST) of the enclosed format. In case of any discrepancy noticed in the quoted percentage, the percentage quoted in words shall be considered. Electricity charges @ 1% shall be deducted in case the vendor uses the electricity from CUJ resources.

Terms and Conditions:-

1. The completion period is 21 days (twenty one days) from the date of issue of work order.
2. The Estimated cost of work is Rs 90330.00 (Rupees Ninety thousand three hundred and thirty only).
However the amount may increase or decrease as per the actual work done.
3. Last date of submission of Quotation is 23/12/2022 at 12:00 hrs
4. Date of Opening of Quotation is 23/12/2022 at 15:00 hrs or as decided by Convenor LPC.
5. Validity of Quotation is 45 days from the date of opening of Quotation.
6. Bidders quoting percentage item wise shall be summarily rejected. Rates are inclusive of all taxes, loading Unloading, transportation Octroi, cess, GST etc. Rates are FOR at site.
7. Statutory deductions like TDS & Labour cess as per applicable rates will be made from the contractor's bill.
8. Rates quoted shall be firm and fix and no escalation shall be provided throughout the currency of the period of work.
9. No advance payment will be made.
10. GST Bill should be provided.
11. CUJ reserves the right to cancel the work before the commencement of work or at any stage of execution if found substandard or not as per required specifications.
12. Payment shall be made through RTGS/NEFT.
13. Work is to be executed as per CPWD Specification 2019 VOL-1&VOL-2 with up-to-date correction slip



जम्मू केंद्रीय विश्वविद्यालय Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

Annexure-1

BOQ for Providing floor finishes and basic toilet facility in Security complex

S No	DSR	Description	Unit	Quantity	Rate(Rs) GST inclusive	Amount(Rs)
1	4.1.11	Providing and laying PCC 1:5:10(1 cement:5 sand:10 40 mm aggregate)	cum	1	5660.45	5,660.45
2		Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :				
	17.4.2	single urinal basin	no	1	3000	3,000.00
3	17.8	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings.	no	1	1500.05	1,500.05
4	17.7.4	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:White Vitreous China Flat back wash basin size 550x 400 mm with single 15 mm C.P. brass pillar tap	no	1	2731.45	2,731.45
8	18.21.2.1	Providing and fixing unplasticised pvc connection pipe with brass unions 45 cm length	m	4	85.2	340.80
9	18.49.1	Providing & fixing C.P brass bib cock of approved quality cnfirming to IS :8931. 15 mm nominal bore	no	1	434.2	434.20
10	17.28.1.1	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 32 mm dia semi rigid pipe.	no	3	90.95	272.85



जम्मू केंद्रीय विश्वविद्यालय Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

11	11.41A.1.1	Providing and laying Vitrified tiles in floor in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, levelling system and rubber mallet for placing the tiles gently and easily. 600mmX600mm tiles	sqm	50	1286.6	64,330
12		12 mm cement plaster of mix 1:6	sqm	20	282	5,640
13		Wall painting with premium acrylic emulsion of interior grade having VOC less than 50 gms per litre of approved brand and manufacture including applying additional coats wherever required to achieve even shade and colour One coat	sqm	80	80.25	6,420
		Total				90,330

Inclusive of GST



जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

Quotation Form

Name of Work: Providing floor finish and basic toilet facility in security complex

Estimated Cost: Rs90330/- (Rupees Ninety thousand three hundred thirty only)

Name of Work	Quote Percentage (Above/At Par/Below) on Estimated cost	
Providing floor finish and basic toilet facility in security complex	In figures	In words
Rs90330 (Rupees Ninety thousand three hundred only) GST inclusive		

Signature & Stamp of the vendor